

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is invited to page 126 of the *Mysore Gazette* dated 7th February 1918, calling for tenders for constructing Police Station and lines for 1 daffadar and 4 men at Sanikere, Challakere Taluk, Chitaldrug District. The last date of tender is 5th March 1918.

Abstract Notification.

The attention of the public is invited to pages 126—127 of the *Mysore Gazette* dated 7th February 1918, calling for tenders for constructing quarters for one Jamadar and lines for one daffadar and 6 constables at Bharmasagara, Chitaldrug Taluk, Chitaldrug District.

Dated 9th February 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 15th March 1918, for constructing Police Station and lines for one daffadar and five constables at Anaji, Davangere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money and be superscribed, "Tender for construction Police Station and lines at Anaji, Davangere Taluk, in default of which, tenders will be rejected."

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing Police Station and lines for one daffadar and five constables at Anaji, Davangere Taluk, Chitaldrug District.

No.	Items of work	Per	Quantity
1	Earthwork excavation gravelly soil for foundation and filling in basement including watering and tamping.	C. yds.	160
2	Burnt stone in clay foundation and basement	C. ft.	6,110
3	Burnt brick in clay superstructure	"	4,814
4	Burnt brick in chunam superstructure	"	1,329
5	Do coping with plastering, etc., complete	R. ft.	287
6	Burnt stone slabs dressed 6" thick and fixed	S. ft.	746
7	Teakwood lock-up door as per plan with iron bars, clamps, etc., complete	"	49
8	Honeywood battened door with iron clamps, hinges, etc., complete	"	616
9	Do windows with iron clamps, hinges, etc., complete	"	89
10	Honeywood ventilators with iron bars expanded metal, etc., complete	"	35
11	Do work wrought and put up complete	C. ft.	164.70
12	Roofing with 1st class Mangalore tiles on teak reapers, etc., complete	Sq.	36.39
13	Ridge tiles set in mortar and cement pointing	R. ft.	109
14	Chunam borders over roof	"	109
15	Teakwood ceiling 1" below rafters for lock-up rooms, complete	S. ft.	210
16	Chunam plastering	Sq.	140.85
17	White and colourwashing, 2 coats	"	140.85
18	Honeywood eave board 8"x1"	R. ft.	482
19	Wood oiling 2 coats to wood work and ceiling	Sq.	15.68
20	Tarring woodwork two coats	"	5.50
21	Teakwood railing in front of station as per plan complete	R. ft.	52
22	Flooring with 1st class Mangalore tiles over 3" concrete bed and cement pointing	Sq.	12.50
23	Do Cuddappa slabs over 3" concrete bed and cement pointing	"	6.68
24	Teakwood gate with iron work, etc., complete	Sq. ft.	10
25	Silicate painting 2 coats	Sq.	23.01
26	Constructing V-shaped drain to lead of water including cement pointing	R. ft.	226
27	Flooring with gravel including watering and tamping	C. yd.	24
28	Teakwood finials	Each	4
29	Do pendants	"	8
30	Cutting grooves and dressing stone pillar	"	2
31	Constructing seats in latrine and fixing drain pipes 1 1/2" diameter, etc., complete	"	7
32	Clearing site and levelling ground	"	"
33	Providing chimney over kitchen	Lump sum	"
34	Providing 1 1/2" diameter galvanized iron pipe to drain water from latrine and kitchen	C. Each	6
35	Constructing cistern in kitchen with burnt stone slabs and cement pointing including plastering to sides, etc., complete.	"	13
36	Providing pestle and mortar stones	"	6

N. ANANDALWAR,
Executive Engineer.